

(1) Number of pages 4
(2) Date of repair _____
(3) Initials of the Referencer _____

TAMIL NADU ARCHIVES

GOVERNMENT OF TAMIL NADU
REVENUE DEPARTMENT

G.O. No.	327	Press.
~~B.P.~~ No.		Mis.
Dated	17 - 1 - 1877	197 .

Not to be folded or roughly handled

Read the following:—

No. 1. W.

No. 141. *Note by the Chief Engineer for Irrigation.*

THE District Engineer, Kurnool, forwards, with his letter marginally noted, an estimate in connection with the Munna-gunta Tank, situated in the Ravelkota Taluk, Kurnool Range.

2. The nature of the work proposed for execution and the heads of account to which it is chargeable are as follow:—

ORDINARY AGRICULTURAL
Original Works.

Forming a natural escape...	Rs. 180
Raising and repairing the bund, also repairing the sluice and loose stone escape	Rs. 80
Total	Rs. 260

3. The following particulars of the Tank are recorded:—

Ayaout area...	Acres 82
Assessment	Rs. 192
Average revenue	" 161
Highest do.	" 191
Expenditure during the previous four years	" 345

The area of the catchment basin is 3 square miles; the maximum flood supply is calculated at 1,170 cubic feet per second, discharging which as surplus there is a rough stone escape 48 feet in length at the western end of the bund, and it is proposed to form a natural escape 142 feet in length as to make an aggregate length of 190 feet available for the surplus discharge.

The bund is low, and it is proposed to raise it 4 feet above weir crest level.

The tank has a sluice which needs trifling repairs, it is otherwise in good order. The rough stone escape also requires slight repairs.

The estimate provides for raising and repairing the bund, also for repairing the sluice and rough stone escape, and it is recommended that sanction be given to it.

(Signed) A. DE C. SCOTT, Major, R.E.,

5th January 1877.

Dy. Chief Engr. for Irrigation,
for Chief Engr. for Irrigation.

To the Secretary to Government, Public Works Department.

*Proceedings of the Madras Government, Public Works Department,
9th January 1877. No. 75.*

No. 142.

ORDER THEREON, 9th January 1877, No. 75.

IRRIGATION, No. 20.

Account.

THE following estimate from the
Kurnool Range, forwarded by the District
Engineer, Kurnool, is sanctioned:—

MUNNAGUNTA TANK.
Irrigation.

Group or Project.	Fund.	Class.	Name of Tank, Canal, or Channel.	Particulars of Work.	Amount.
..	Ordinary Agri- cultural.	Original Works Repairs ..	Munnagunta Tank.	1. Natural escape .. 2. Repairing bund, sluice and escape.	Rs. 150 80

To be carried out by the Public Works

Department Officer in charge, Kurnool Range.

2. This sanction has been register

No. 257—I. of 1876-77.

(True extract.)

Ch. V. S. Major-General, R.E.,
Secretary to Government.

To the District Engineer, Kurnool.

- „ Collector of do.
- „ Chief Engineer for Irrigation.
- „ Examiner of Public Works Accounts.
- „ Revenue Department. ✓

Exd. S. T. Austin.

Spare Copies

327
2/2

Revenue Department

N^o 546

Govt. of 1877 Madras

PUBLIC WORKS.

To

THE DISTRICT ENGINEER,
KURNOOL.

cc. cc. cc.

Dated January 9th.

Issued

Recd. — 17th

Encl.

G. O., 3th January 1877, No. 75.

JANUARY.

Nos. 141-142.

N^o 327

Comm. to the
Board of Revenue

Munnagunta Tank, Kurnool District —
Estimate of Rupees 260 for repairs to the
—, sanctioned.

17 Jan 77.

8 L. O. O. D. of 1877 Jan 1

Office Copy