Archives 1—10,000—6-10-76.

(1) Number of pages 4

(2) Date of repair May 86

(3) Initials of the Referencer LDB

TAMIL NADU ARCHIVES

GOVERNMENT OF TAMIL NADU

P W D Rev DEPARTMENT

G.O. No.	335	Press.
B.P. No.		—Mis.—

Dated 15 (4) 6 1977.

Not to be folded or roughly handled

GOVERNMENT OF MADRAS.

PUBLIC WORKS DEPARTMENT.

4th June 1877, No. 58 I.

Irrigation.

Account.

Read the following :—

No. 35 I.

No. 9. *Note by the Chief Engineer for Irrigation.*

In G.O., of the 16th August 1875, No. 2,346, certain estimates were sanctioned for the Veerajeeconum large* tank and Pootharyt pending the settlement of the question whether the two tanks should be amalgamated, or the larger retained, or the two kept as hitherto with divided waterspreads. In his letter No. 3,938 of the 12th February last, the Superintending Engineer reported that, on the score both of capacity and to avoid submerging land above the waterspread of the large tank, it would be better to make the two tanks into one and to abandon the separating bund; and in a letter dated the 12th March last, he has shown that the cost of repairing the tanks separately* and of amalgamating† them would be very nearly the same, but that of the latter slightly less. These estimates are considerably less than those amounting to Rupees 4,020 formerly submitted, and it is recommended that the estimate for forming the two tanks into one be sanctioned. This sanction will supersede that given in the Government Order above quoted.

* Rupees	1,420
† ,,	350
Total ...	1,770

* Rupees	3,445
† ,,	3,435
Difference ...	10

Fort St. George,
28th May 1877.

(Signed) JOHN MULLINS, Lt.-Col., R.E.,
Chief Engineer for Irrigation.

To the Joint Secretary to Government, Public Works Department, Irrigation Branch.

No. 10. ORDER THEREON, 4th June 1877, No. 58 I.

The following estimate from the Superintending Engineer, Chingleput, is submitted,— Chingleput Range forwarded by the

Amalgamating Veerajeconum large tank with Poothery tank.

Head of Service.—Irrigation.

Group or Project.	Fund and Main Head.	Class.	Name of Tank.	Particulars of Work.	Amount.
	Ordinary Agricultural Irrigation.	Original Works.	Veerajeconum large and Poothery tanks.	Escape	Rs. 210
				Sluice	290
					500
		Repairs ...		Repairing the bund ...	1,600
				Repairing a sluice ...	300
				Weir	145
					2,045
				Total ...	Rupees 2,545

To be carried out by the Public Works Department Officer in charge No. 3 or Chingleput Range.

2. This sanction has been registered as No. 59 I of 1877-78 and cancels the sanction accorded in G. O. No. 2,346 of 16th August 1875.

(True Extract.)

Lt.-Col., R.E.,
Joint Secy. to Govt., P.W.D.,
Irrigation Branch.

To the Superintending Engineer, Chingleput.
" Collector of Chingleput.
" Chief Engineer for Irrigation.
" Examiner of Public Works Accounts.
" Revenue Department.

Fwd. E. C. Shunkar.
Spare Copies

335

Kansas Oil Lease
$2.00

Oil, Mineral and Royalty Deed

Dated this 15th day of Nov. A.D. 1926

Grantor, Mrs. Mary Hayes

Grantee, Ray Reeves

Consideration, $2.00 and other valuable consideration

Recorded in Book 210, Page 357

Grantee's Address, Ray Reeves, Wichita, Kansas