

(1) Number of pages 2
(2) Date of repair 11. 8. 81
(3) Initials of the Referencer _____

TAMIL NADU ARCHIVES

GOVERNMENT OF TAMIL NADU

Revenue

DEPARTMENT

G.O. No.	4603	Press.
B.P. No.		Mis.
Dated	16. 8. 1877	197

Not to be folded or roughly handled.

PUBLIC WORKS DEPARTMENT.

Irrigation.

No. 112 I.

The Officiating District Engineer, Tinnevely, forwards, with his letter marginally noted, an estimate in connection with the Sungampatty Tank situated in the Ottapidaram Talug, Tinnevely Range.

ORDINARY AGRICULTURAL.

IRRIGATION.

Original Works.

						RS.
Constructing a masonry weir	...	...	...	...	...	284

Repairs.

Raising and repairing the bund	...	...	...	...	...	203
Repairing the irrigation sluice	...	...	...	...	...	86

Total ... 573

Ayacut area ...	...	...	...	...	...	...	23 Acres.
Assessment ...	...	...	...	...	...	...	87 Rupees.
Average revenue ...	...	...	...	...	...	...	78 "
Highest do. ...	...	...	...	...	...	...	89 "
Expenditure during the previous four years	...	...	...	...	...	...	Nil.

The estimate provides for these additions and repairs.

As the weir will be on rock, there will be no necessity for the apron and retaining wall provided for in the plan and estimate. Instead of masonry wings also, the faces of the bank at the ends of the weir may have rough-stone revetment, the body wall being carried into the bank and stepped up as shown on the "design for a cheap surplus weir"—Design No. 4, Circular No. 67. This will reduce the estimate for the work to Rupees 165. With this alteration the estimate is recommended for sanction.

35 cubic yards stone in mortar, at 4 Rs. ...
4 do. revetment, at 2 Rs. ...
Excavating and filling ...
Contingencies ...

Total ... 165

FORT ST. GEORGE,
26th July 1877.

(Signed) G. T. WALCH,
Ag. Dy. Chief Engr. for Irrigation,
for Chief Engr. for Irrigation.
to the Joint Secretary to Government, Public Works Department, Irrigation Branch.

No. 17. ORDER THEREON, 4th August 1877, No. 218 I.

The following estimate from the Tinnevelly Range forwarded by the Officiating District Engineer, Tinnevelly, is sanctioned:—

SUNGAMPATTY TANK.

Head of Service—Irrigation.

Group or Project.	Fund and Main-head.	Class.	Name of Tank.	Particulars of Work.	Amount.
None.	Ordinary Agricultural Irrigation.	Original Works. Repairs ..	Sungampatty Tank.	1. Weir 2. Repairing bund ... 3. Do. sluice ... Total ...	Rs. 165 204 86 455

To be carried out by the Public Works Department Officer in charge Tinnevelly Range.

2. This sanction has been registered as No. 117 I of 1877-78.

(True Extract.)

G. T. Walch
Joint Secy. to Govt., P.W.D.,
Irrigation Branch.

To the District Engineer, Tinnevelly.
" Collector of Tinnevelly.
" Chief Engineer for Irrigation.
" Examiner of Public Works Accounts.
" Revenue Department.

Exd. J. W. Fischer.
Spare Copies

12

103698
IRRIGATION.

Govt. of 1877 Madras.

PUBLIC WORKS.

To

THE DISTRICT ENGINEER,
TINNEVELLY,
&c., &c., &c.

Dated August 4th.

Issued

Recd. 15 August

Encl.

G. O., 4th August 1877, No. 218 I.

To the

AUGUST.

Nos. 16-17.

Sungampatty Tank, Tinnevely District.—
Sanctions estimate of Rupees 455 for repairs,
&c., to the —

Rs. 4603
Comd. to the
Board of Revenue
16 Aug 77

1904 Aug 21-22
(6-11-22)