

(1) Number of pages d sheets
(2) Date of repair _____
(3) Initials of the Referencer _____

TAMIL NADU ARCHIVES

GOVERNMENT OF TAMIL NADU

Revenue DEPARTMENT

G.O. No.	<u>6433</u>	Press.
B.P. No.		Mis.
Dated	<u>28. 11. 1877</u>	197

Not to be folded or roughly handled.

GOVERNMENT OF MADRAS.
PUBLIC WORKS DEPARTMENT.

19th November 1877, No. 505 I.

Irrigation.

Read the following paper :—

No. 63. From Colonel F. J. MOBERLY, R.E., Superintending Engineer, Chingleput, to the Chief Engineer for Irrigation, dated St. Thomas' Mount, 20th August 1877, No. 1,930.

I HAVE the honor to forward, for the sanction of Government, an estimate, amounting to Rupees 845, for repairing the Vallum tank of the Kolavoy group, Chingleput taluq, in No. 3 or Chingleput Division.

No. 231 I.

No. 63-A. *Note by the Chief Engineer for Irrigation.*

THE Superintending Engineer, Chingleput, forwards, with his letter marginally noted, an estimate in connection with the Vallum tank of the Kolavoy tank group, situated in the Chingleput taluq, Chingleput range.

2. The nature of the work proposed for execution and the heads of account to which it is chargeable are as follow :—

ORDINARY AGRICULTURAL.
IRRIGATION.

Repairs.	RS.
Raising and repairing the bund, repairing three Irrigation sluices, improving the calingulah, and forming an escape planted with grass	845
Total ...	845

3. The following particulars of this tank are recorded :—

Ayacut area...	117 Acres.
Assessment ...	542 Rupees.
Average revenue ...	575 "
Highest do. ...	640 "
Expenditure during the previous four years ...	Nil.
Average cultivation per square mile ...	82.7 Acres.

This tank is situated in the Kolavoy basin and effects the railway at the 34th mile. It has no high lying tanks.

The area of the catchment basin is $1\frac{1}{2}$ square miles, the maximum flood supply is calculated at 737 cubic feet per second, for discharging which as surplus there is a calingulah 23.5 feet in length with two notches each 4.75 feet long and 6 inches deep, the effective length of this work is 9.5 feet, and in order to make the whole length available it is proposed to convert the calingulah into a flush weir by building up the notches. It is also proposed to form a grass planted escape 109 feet long at same level, making an aggregate length of 132.5 feet available for the surplus discharge.

The bund of this tank is much eroded, and the inner slope and revetment damaged by the floods of 1872 and 1874.

The tank has three irrigation sluices all of which are in need of repairs.

The estimate provides for raising and repairing the bund, repacking the revetment which is 2.5 feet below F.T.L., planting the space between the top of the revetment

and F.T.L. with tank grass, forming an escape planted with grass, repairing three irrigation sluices, and converting the calingulah into a weir.

In this part of the district stone is abundant, and, as the tank is one of a group and is above the railway, it will be better to provide an escape of the form shown in design No. 5, circular No. 67, which will cost for a length of 56 feet about Rupees 224.

Rupees 24 for grass planting have been deducted from the repair estimate, and Rupees 224 allowed for an additional surplus weir.

The following statement shows the proposed distribution of the outlay recommended for sanction to the debit of the several heads of account involved:—

HEAD OF SERVICE.—IRRIGATION.
Fund—Ordinary Agricultural.

Name of System or Group.	Distinguishing Number or Letter of Group.	Name of Tank or Channel.	Description of Work.	Main-head.	Class.	Amount of each Item.	Amount to be separately accounted for.
Kolavoy Group.	...	Vallum Tank.	Repairing bund and three sluices, improving calingulah.	Irrigation.	Repairs.	Rs. 821	Rs. 821
			Constructing a surplus weir.		Do. Original Works.	224	224

FORT ST. GEORGE,
8th November 1877.

(Signed) P. MONTGOMERIE, Major, R.E.,
Ag. Dy. Chief Engr. for Irrigation,
for Chief Engineer for Irrigation.
To the Joint Secretary to Government, Public Works Department, Irrigation Branch.

No. 64.

ORDER THEREON, 19th November 1877, No. 505 I.

The following estimate from the Chingleput Range forwarded by the Superintending Engineer, Chingleput, is sanctioned:—

Head of Service.—Irrigation.
Vallum Tank.

Work.—Repairing bund and three sluices and improving calingulah, Repairs Rupees 821.
Constructing a surplus weir, Original Works Rupees 224.

To be carried out by the Public Works Department, Officer in charge, Chingleput Range.

2. These sanctions have been reported as No. 257 I of 1877-78.

(abstract.)

P. Montgomery

Major, R.E.,
Ag. Under Secy. to Govt., P.W.D.,
Irrigation Branch.

To the Superintending Engineer, Chingleput.
" Collector of Chingleput.
" Examiner of Public Works Accounts.
" Chief Engineer for Irrigation.
" Revenue Department.

Exd. E. C. Shunker.

14 Spare Copies

104945
IRRIGATION.

Gobt. of 1877 Madras.
PUBLIC WORKS.

TO THE SUPERINTENDING ENGINEER,
CHINGLEPUT,
&c. &c. &c.

Dated November 19th.

Issued

Recd. 27 November, 1877.

G. O., 19th November 1877, No. 505 J.

NOVEMBER

Nos. 63-64

11. *Commenced by 25th Oct.*
Water Tank, Chingleput District. — San-
ctions estimate for repairs to the —

Subd. 33
Comm. to the
Board of Revenue