

Public Works (1894) Department.

RAILWAY BRANCH.

G.O., No. 647 R

DATED 4th December

[Despatch Abstract.]

Girder bridges. — Estimate of Rs 24,985 for strengthening some of the — on the north-west and South-west lines, Madras Railway, sanctioned.

RAILWAY.

Govt. of {1894} Madras.
PUBLIC WORKS.

Dated December, 4th.

Recd.

Encl.

G.O., 4th Dec. 1894, No. 647 R.

DECEMBER.

Girder Bridges

Estimate of Rs. 24,985 for strengthening
some of the — on the North-west and South-
west lines, Madras Railway, sanctioned.

No 7759
694

MADRAS RAILWAY.

AGENT AND MANAGER'S OFFICE.

Madras, 5th September 1894

From

The Agent and Manager.

To

The Consulting Engineer for Railways.

Sir,

Adverting to paragraph 2 of
your letter of 2136 of the 7th July last, I have
the honour to forward herewith an estimate
for strengthening some of the girder bridges
spanned by weak girders on the North-
west and South-west Lines and to request that
the sanction of Government may be conveyed
to me for the required outlay of Rs. 24,985
chargeable to Revenue.

The estimate provides for strengthening
these girders up to the full extent
required by the Government rule as sug-
gested in your letter above quoted.

The following extract from a letter
from the Chief Engineer contains a descrip-
tion of the method of strengthening
upon in the case of the several bridges
in the estimate.

1931

11. 2. 11.

10.

三

I. 297 spans of 6 feet rail girders. These will be strengthened by duplicating and the insertion of the additional girders can be easily carried out.

II. 13 spans varying from 20 to 24 feet. These will be strengthened by additional plates added to the top and bottom flanges.

III 3 single spans of 50 feet. These will be strengthened by halving the spans by means of a central masonry pier 3 feet in width which it is found will not interfere with the waterway. Two of these bridges are floored and the third has rock foundation and the highest recorded floods are comparatively small compared with the head-way of the bridge.

The provision for contingencies has been made at 10 instead of at 5 percent as the Chief Engineer considers it necessary owing to the miscellaneous nature of the work.

Information as to provision in the budget and date on which sanction will be given on the estimate.

I have the honour to be
Your most ^{Sir} obed^t Serv^t

Louis. S. M. 188

agent & manager

PUBLIC WORKS DEPARTMENT,
RAILWAY BRANCH.

READ the following

Sanctioned.

2. This sanction has
been registered as No 15
of 1894-95.

DESPATCHED
17 DEC 94

—his Excellency of the Gov.
for purposes of approbation

2. The Agent or man: h. Ry ✓
- Ex. G. Ry. p. 10: ✓

The Agent and Manager.
 The Consulting Engineer.
 For Railways.
 No. 11, Great Street, London, W.

MADRAS RAILWAY.

From
The Agent and Manager
The Consulting Engineer
for Railways.

Plan for strengthening
Gordon bridge on the
Atlantic Railway