

- (1) Number of pages 4
(2) Date of repair 8.1.1970
(3) Initials of the Referencer _____

MADRAS RECORD OFFICE

GOVERNMENT OF MADRAS

Revenue DEPARTMENT

G.O. No.	19131	Press
B.P. No.		Mis. ✓
Dated	14.8.1876	196

Not to be folded or roughly handled

DL

Proceedings of the Madras Government, Public Works Department,
25th July 1876. No. 1,882.

Read the following:—
No. 418. W.

No. 418. Note by the Chief Engineer for Irrigation.

THE Officiating District Engineer, Tinnevely, forwards, with his letter marginally No. 153, dated 18th March 1876. an estimate in connection with the Chuttrum Puthucolum tank situated in the Tinnevely taluq, Tinnevely range.

2. The nature of the work proposed for execution and the heads of account to which it is chargeable are as follow:—

Ordinary Agricultural.		RS.
Reconstructing the masonry weir. Repairs	...	3,095
Raising the bund at the return from the surplus weir. Repairs	...	150
Total	...	3,245

3. The following particulars of this tank are recorded:—

Ayacut area.	...	477
Assessment.	...	4887
Average revenue.	Nil.	
Highest do.	...	

Expenditure during the previous four years. Rupees 2,430.

The area of the catchment basin is 12 square miles; the maximum flood supply is calculated at 2,300 cubic feet per second for discharging which, as surplus, there is a weir 280 feet in length in a dilapidated condition, it is proposed to dismantle and reconstruct it on nearly the same site reducing the length to 200 feet, and to raise the return of the bund to $4\frac{1}{2}$ feet above F.T.L. The work has been proceeded with on emergency.

4. The cut stone on the face of the weir might probably be dispensed with, and it will, as far as practicable, be omitted from the work in progress in accordance with instructions already issued to the District Engineer. It will be required for the crest and vents. The estimate is recommended for sanction.

OOTACAMUND,
18th July 1876.

(Signed) A. DEC. SCOTT, Major, R.E.,
Dy. Chief Engineer for Irrigation,
for Chief Engineer for Irrigation.

To the Secretary to Government, Public Works Department.

No. 419. ORDER THEREON, 25th July 1876, No. 1,882.

IRRIGATION, No. 44-A.

Account.

THE following estimate from the Tinnevely range, forwarded by the Officiating District Engineer, Tinnevely, is sanctioned:—

Reconstructing the masonry weir, and raising the bund at the return from the surplus weir of the Chuttrum Puthucolum tank.

Irrigation—Ordinary Agricultural.

RS.	
Repairs	...
Total	...

(2) Date of repair

(3) Initials of the Referencer

*Proceedings of the Madras Government, Public Works Department,
25th July 1883. No. 1,882.*

2. This sanction has been registered No. 71-I. of 1876-77.
(T. tract.)

W. H. French

Colonel,

Offg. Under Secy. to Govt., P.W.D.

To the District Engineer, Tinnevely.
„ Collector of do.
„ Examiner of Public Works Accounts.
„ Chief Engineer for Irrigation.
„ Revenue Department.

Exd. W. H. French.

1/3 Spare Copies *sent to the office*

(2) Date of repair _____

(3) Initials of the Referencer _____

No 3270
Revenue 1876 Depts
Govt. of 1876 Madras.

PUBLIC WORKS.

To
THE DISTRICT ENGINEER.

TINNEVELLY.

&c., &c., &c.

Dated July 25th.

Issued

Recd.

11 Augt 1876

Encl.

G. O., 25th July 1876, No. 1482.

JULY.

Nos. 418-419.

By Mr

Chittam Puthucolum Tank, Tinnevelly
District.—Sanctioning estimate of Rupees
2,243 for reconstructing the surplus weir of
do —

No 1913

communicated to the District Engineer

11 August 1876

New No. Sectt. I (i)-1—Old No. M.R.O. 1—10,006—10-6-68.

- (1) Number of pages _____
(2) Date of repair _____
(3) Initials of the Referencer _____