M.R.O. 14—13,000—27-9-24.

MADRAS RECORD OFFICE.

Government of Madras.

Revenue **DEPARTMENT.**

G.O. No. 2752 Press ~~Mis.~~

369-370

Dated 20 — 11 — ~~19~~ 1867

Not to be folded or roughly handled

2752 Jdg

Proceedings of the Madras Government, Revenue Department, 20th November 1867.

No. 369. Read the following Proceedings of the Madras Government in the Public Works Department:—

Sanctioning estimate for digging a new cut to Yanam bank canal, between 19th and 20th miles, in the Godavery District. } (Here enter 15th November 1867, No. 3,529.)

No. 370. ORDER THEREON, 20th November 1867, No. 2,752.
Communicated to the Revenue Board.

Irrigation, No. 14.

(True Extract.)
(Signed) F. H. WILKINSON,
Acting Under Secretary to Government.

To the Board of Revenue, with Proceedings Public Works Department, No. 3,529.

Exd. S. T. Augustin.

No. 295. Read the following letter from the Acting Superintending Engineer, 1st Division, to the Secretary to Government, Public Works Department, dated Camp at Dowlaishweram, 30th October 1867, No. 174 :—

1. I have the honor to submit for sanction an estimate, amounting to Rupees 2,000, for digging a new cut to Yanam bank canal, between 19th and 20th miles.

1 Copy of a letter from Mr. Sage.
1 Survey.
1 Estimate.

2. The necessity for the proposed outlay is explained in the enclosed copy of a letter* from Mr. Executive Engineer Sage, in whose range the canal is.

* No. 724, dated 28th October 1867.

3. In the event of the proposed work being sanctioned for immediate execution, I shall endeavour to provide funds for it by transfers from one head to another.

From the Officer in charge of No. 1 or Eastern Delta Range, Godavery District, to the Superintending Engineer, 1st Division, dated Dowlaishweram, 28th October 1867, No. 724.

1. I have the honor to forward, herewith, a plan and estimate for making a new cut between 19th and 20th mile on Yanam bank canal, amounting to Rupees 2,000. The necessity for the work is as follows :—First, the river during freshes this year took a complete set on to the river bank, and ate in about 100 feet, as shown at point marked × on plan and also by dotted line ; it destroyed the river embankment, and the water is only held in canal by a ring bank, which it will not be safe to have as part of the river embankment.

2. The accompanying estimate provides for digging a new cut for a length of 850 yards, and converting the canal bank (new) next river into river embankment.

3. As it is of importance this cut should be dug before next freshes, I have the honor to request you will obtain sanction to the same as early as possible.

No. 296. ORDER THEREON, 15th November 1867, No. 3,529.

IRRIGATION, No. 16.

Sanctioned for execution, on the understanding that the outly is hereafter adjusted by the Superintending Engineer.

(True Extract.)

Colonel, R. E.,
Secretary to Government.

To the Superintending Engineer, 1st Division.
" Accountant General.
" Controller of Public Works Accounts.
" Revenue Department.

Exd. S. T. Augustin.

Peramne 1867 - Offr &c
to forward Estimate
No 3126.

Sanctioning the
Construction of the
Ghoolaree Dist.

Noted 15th 3 hours
Received 16th 1867.

No 3529.

Sanctioning Estimate for dredging a new cut to Goluckmunny Canal between 19th & 20th miles in the Godaveery Dist.

No 2752. 20 Hours

Will Order

No 369-37

No 2752.

Comm. Ex.

Ex. Rec. 18.1

Ch

20th Hours 67

Mr Espin Take Dirg Instructions Rec Mrs No 3529 Dated 15th