M.R.O. 14—13,000—27-9-24.

MADRAS RECORD OFFICE.

Government of Madras.

Revenue **DEPARTMENT.**

G.O. No. 2799	Press ~~Mis.~~
470.471	
Dated 25-11-1987	

Not to be folded or roughly handled

/17

Proceedings of the Madras Government, Revenue Department, 25th November 1867.

No. 470. Read the following Proceedings of the Madras Government in the Public Works Department :—

Sanctioning estimate for cutting a new head to the Mundapetta canal in Godavery District. } (Here enter 21st November 1867, No. 3,598.)

No. 471. ORDER THEREON, 25th November 1867, No. 2,799.

Irrigation, No. 15. Communicated to the Revenue Board.

(True Extract.)

(Signed) F. H. WILKINSON,
Acting Under Secretary to Government.

To the Board of Revenue, with Proceedings Public Works Department, No. 3,598.

Exd. S. T. Augustin.

No. 431. Read the following letter from the Acting Superintending Engineer, 1st Division, to the Secretary to Government, Public Works Department, dated Camp at Dowlaishweram, 7th November 1867, No. 181:—

1 Survey Plan.
1 Estimate.
1 Copy of Mr. Sage's letter, No. 698, dated 19th October 1867.

1. With reference to Government Order, No. 3,369, dated 31st October 1867, calling for further information before sanctioning a new head to the Mundapetta Canal, estimated to cost Rupees 1,000, I have the honor to inform you that at present less than 40,000 cubic yards per hour flow from this canal, which irrigates directly over 15,000 acres, requiring a maximum supply of 35,000 yards of water; in addition to this 15,000 yards per hour is required to supplement the supply of water in the Coringa Canal both for purposes of irrigation and navigation. There are also 10,000 acres of land to be gradually brought under wet cultivation from the Mundapetta Canal, so that eventually the first reach of four miles in length must be widened; this is not, however, immediately so very necessary, and, moreover, so much earth-work has already been sanctioned that it could not be done this working season; but doubtless it is desirable that a new head, to cost only Rupees 1,000, and that will admit probably at least a fifth more water, should be executed this working season; at present a comparatively small channel branching off at right angles, the water does not enter it with a natural flow but in eddies.

No. 432. ORDER THEREON, 21st November 1867, No. 3,398.

IRRIGATION, No. 20.

1. Under the further explanations now submitted by the Superintending Engineer of the 1st Division, the Government sanction the estimate of Rupees 1,000 for cutting a new head to the Mundapetta Canal in the Godavery District.

2. The work may be proceeded with if the Superintending Engineer can provide the requisite funds.

(True Extract.)

Colonel, R. E.,
Secretary to Government.

To the Superintending Engineer, 1st Division.
" Accountant General.
" Controller of Public Works Accounts.
" Revenue Department.

Exd. F. R. Bantleman.

Revenue 1867. Office
bro of Govt for Nov
No. 3188.

Proceedings of the
P. W. Office &c.

Dated 21st Nov 2 hours
Received 23rd 1867.
No. 3598.

Sanctioning Estimate for cutting a new head to the Mundapetta Canal in Godavery District.

With Order
No. 2799 - 25 hours

No. 2799.

Commtd to the Revenue Board.

25th hours/67

12 Copies Forwarded of Revenue with Ord No. 2799 Dated 26/11/67