M.R.O. 14—13,000—27-9-24

MADRAS RECORD OFFICE.

Government of Madras.

Revenue **DEPARTMENT.**

G.O. No. 2813 Press Mis.

499-500

Dated 26-11-1867.

Not to be folded or roughly handled

Proceedings of the Madras Government, Revenue Department,
26th November 1867.

No. 499. Read the following Proceedings of the Madras Government in the Public Works Department :—

Sanctioning estimate for improving the Allalum channel in the Oossoor talook, Salem District. } (Here enter 23rd November 1867, No. 3,633.)

No. 500. ORDER THEREON, 26th November 1867, No. 2,813.

Irrigation, No. 16. Communicated to the Revenue Board.

(True Extract.)

(Signed) F. H. WILKINSON,
Acting Under Secretary to Government.

To the Board of Revenue, with Proceedings Public Works Department, No. 3,633.

Exd. F. R. Bantleman.

No. 503. Read the following letter from the Superintending Engineer, 5th Division, to the Secretary to Government, Department Public Works, dated Ooloondoorpett, 12th November 1867, No. 173 :—

2 Plans.
1 Abstract Estimate.
1 Specification.
1 Revenue Statement.

1. I have the honor to forward, for the sanction of Government, and entry in the ensuing year's Budget, an estimate of Rupees 4,680 for improving the Allalum channel in the Oossoor talook of the Salem district.

2. The estimate provides for widening and straightening the existing channel, correcting the slope of the bed, building sluices for the distribution of the water, and aqueducts for carrying across it several jungle streams, which at present carry large quantities of sand into the channel; also for extending the channel, with a view to bringing more land under cultivation.

3. The plans and estimate have been approved by the Collector, who, in returning them to me, has remarked that the expected increase should be nearly 80 Rupees less than the amount in the Revenue Statement, as the Punjah assessment of the main lands should not have been taken into account.

No. 504. ORDER THEREON, 23rd November 1867, No. 3,633.

IRRIGATION, No. 23.

1. With this letter the Superintending Engineer of the 5th Division submits an estimate amounting to Rupees 4,680, for the improvement of the Allalum channel in the Oossoor talook of the Salem district for a distance of 3⅓ miles, and for extending the channel 1⅓ miles with the view of bringing additional land under cultivation. The estimate provides further for the construction of a sufficient number of distribution sluices, and of six small aqueducts for conveying the drainage water across the channel.

2. The expected increase of revenue has been calculated by the Collector at about 850 Rupees per annum, or upwards of 18 per cent. upon the proposed outlay.

3. As the works are likely to be beneficial, and offer a fair promise of being remunerative, the Government sanction the estimate of Rupees 4,680 submitted by the Superintending Engineer, and will allot funds for the execution of the work during the ensuing official year.

(True Extract.)

L. Anderson
Lieut.-Colonel, R. E.,
Joint Secretary to Government.

To the Superintending Engineer, 5th Division, with two Plans and Specification.
„ Controller of Public Works Accounts.
„ Accountant General.
„ Revenue Department.

Exd. T. O'Connor.

Revenue 1867 - Dep't
Re of Gov't for Hour
No. 3206.

Proceedings of the
P. M. Dep't.

Dated 23d. 3 hour
Received 25th 1867.
No. 3633.

No. 2813.

Comm'd to the
Revenue Board.

26th. Hour

Sanctioning Estimate for improving the Alalum Channel in the Assootaloo R., Salem District.

With Order
No 2813. 26 Hour

Papers Letter B. of Revenue with Rec'd No. 3633 Dep't R. 27

No. 499-500
Letter B