

Public Works (1890) Department.

G.O., No. 871.72

DATED 24th October 1896

[Despatch Abstract.]

Cattle Crossing: Estimate of Rs. 1400 for
constructing a — at 44 miles, 6 bullocks & 510
out of Commanur Canal, Krishna Deekshin
Delta, sanctioned.

~~110~~
6

T.C. 24/10

26/10

[illegible]

G.O.	No.	Department	Date	G.O.	No.	Department	Date

Approving the recommendation of the Chief Engineer for Irrigation that a — to ascertain the run off from the catchment basin of rivers or streams be indented for from England for use in the IV. Circle.

GOVERNMENT OF MADRAS.
PUBLIC WORKS DEPARTMENT.

General.
Account.

READ—the following papers:—

From J. HANNAN, Esq., Superintending Engineer, IV Circle, to the Chief Engineer for Irrigation, dated 11th August 1896, No. 160 I.

There is at present no means of gauging rivers or streams to ascertain the run off from their catchment basins, yet the success of any irrigation project depends entirely on the degree of accuracy with which the run off is estimated.

2. The usual practice is to employ a registrar on Rs. 8 or Rs. 10 to read a weir gauge. The results so obtained are worthless.

3. Automatic registers should be supplied to the department, capable of registering from, say, 1 inch to 6 feet, worked by clock work, which would not require winding oftener than once in, say, 10 days, and they should give discharge diagrams for that period.

4. I have the honour to request that you will be good enough to take the necessary steps with a view to the supply of such gauges at an early date.

To the Engineer, Madras Municipality, dated 25th August 1896, No. 363 M.

From S. LOANE, Esq., Acting Engineer, Madras Municipality, to the Chief Engineer for Irrigation, dated 7th September 1896, No. 964 W. W.

With reference to your letter No. 363 M. of the 25th ultimo, I have the honour to inform you, that the weir gauge fitted at the head of the Red Hills water-supply channel was made by Messrs. W. F. Stanley & Co. of London. This gauge has been in use at the above site for about eleven years and has had slight repairs done to it on five occasions.

The gauge is composed of a float on which a pencil is carried, a drum on which the diagram form is fixed, and a clock which works the drum.

The drum revolves once round in 24 hours, and as the float rises or falls, the pencil fixed on it indicates on the form the depth over knife edge of weir. We have also two other gauges—one at our Ráyapuram pump well, and the other at the outfall sewage channel in Washermanpet. These were made by Messrs. Bailey & Co., Hydraulic Engineers, Manchester, and, although of somewhat different construction, work on the same principle as that on the water-supply channel.

All three gauges have worked satisfactorily.

No. 174 I.

Submitted to Government with a recommendation that a gauge be indented for from England. Messrs. Bailey & Co., Hydraulic Engineers, Manchester, could probably supply or make a gauge to suit the Superintending Engineer's requirements.

(Signed) R. R. E. DRAKE-BROCKMAN, Col., R.E.,
Chief Engineer for Irrigation.
24th Sept. 1896.

ORDER—No. 860 I., dated 23rd October 1896.

Approved.

2. The General Superintendent, Public Works Stores, will submit a special indent for a gauge of the kind required for transmission to the Director-General of Stores, India Office, for early compliance.

(True Extract.)

Under Secretary to Government,
Irrigation Branch.

To the Chief Engineer for Irrigation.
" Chief Engineer, Public Works Department.
" Superintending Engineer, IV Circle.
" V
" Examiner, Public Works Accounts.

Ed. T. K. Narayana Aiyangar.

10. 860 I. of 23rd October 1896
 PROCEEDINGS OF THE MADRAS GOVERNMENT.

Under date the

Read the following

From the Super. Engineer, Fourth Circle, (N^o. 160-I dated 11 Aug. 1896.)
To the Engineer, Madras Municipality, (N^o. 363-M. dated 25 Aug. 1896.)
From the — do — do — (N^o. 964 dated 7 Sept. 1896.)

No 174 I of 24th Sept 1896.

Submitted to Government with
 a recommendation that a pump
 be indented for from England.
 Messrs. Bailey & Co., Hydraulic Engineers,
 Manchester, could probably supply
 or make a pump to suit the
 Super. Engineer's requirements.

Order thereon.

Approved.

2. The General Superintendent, Public
 Works Stores, will submit a special
 indent for a pump of the kind
 required for transmission to the
 Director-General of Stores, India Office,
 for early compliance.

7/11/96
9.54 11.10.96
 To the Chief Eng^r for Irrigation.
 - Chief Engineer P. W. D.
 - Super. Engineer, Fourth Circle.
 - Sup^r Engineer, Fifth Circle.
 - Examiner, P. W. Accts.

Public Works (189⁶) Department.

CURRENT No. 8806

Order

From

*The Chief Engineer
for Irrigation*

No. 174-D

Dated 24-9-96

Received 1-10-96

Enclosures 3

Spare copies

SUBJECT.

*Weir gauge required
for use in South side*

W.H.

"G"

10-96

028462 L.C. 5/10

[illegible][illegible]

CURRENT No. 534. H.

Order

The Engineer
Madras Municipality

No. 964

ated 7-7-96

Received 8-9-96.

enclosures

pare copies

Weir gauge fitted at
the head of the Red
Hills water supply
Channel --- I wish
particulars of the
with name of maker.

[illegible]

G.O.	No.	Department.	Date.

21. The

CHIEF ENGINEER
FOR IRRIGATION.

8- SEP. 96

No.

Public Works (1896) Department.

CURRENT No.

Order

From

*The Chief Engineer
for Irrigation*

No. 363. M.

Dated 25—8—96.

Received

Enclosures

Spare copies

SUBJECT.

*Clockwork apparatus
in use at the head of
the Municipal Channel
at Red Hills — requests
to furnish this office
with particulars of the
— with name of makers
as it is under con-
sideration to procure
some form of automatic
discharge register
apparatus.*

*Q. 5.3
8806/26*

[illegible][illegible]

8609

28/8
18/6