# Revenue (1894) Department.

MISCELLANEOUS SERIES.

G.O., No. 2640

DATED 22nd June.

---

[Despatch Abstract.]

Communicating to the Board of Revenue, Proc: P. W. Dept. sanctioning the Estimate of Rs 2,600 for fixing iron cast pipe sluices along the Nerur channel, Coimbatore &c.

Revenue 1898 Department

## BACK PAPERS.

| G.O. | No. | Department. | Date. | G.O. | No. | Department. | Date. |
|---|---|---|---|---|---|---|---|
| | | | | | | | |

## FURTHER PAPERS.

| G.O. | No. | Department. | Date. | G.O. | No. | Department. | Date. |
|---|---|---|---|---|---|---|---|
| | | | | | | | |

IRRIGATION.
ACCOUNT.

# Government {1898} of Madras.

## PUBLIC WORKS.

*Recd.* 16 June } 1898.
*Regd.* 17 in }

*Enclosures*

*Spare copies*

**G.O., No. 433 I., 3rd June 1898.**

G.O. misc. 2640 d/22nd June 98.
Communicated to the Board of Revenue

**JUNE.**

Lr. dt. 20/6/98
Letter Board's Rc. L.R. & A. Dated 24.6.98.

### Pipe sluices

Estimate of Rs. 2,600 for fixing cast iron — along the Nerur channel, Coimbatore division, sanctioned.

GOVERNMENT OF MADRAS.

PUBLIC WORKS DEPARTMENT.

**Irrigation.**
**Account.**

READ—the following papers:—

From A. H. GARRETT, Esq., Superintending Engineer, IV Circle, to the Chief Engineer for Irrigation, dated Ootacamund, 26th April 1898, No. 81/I.

I have the honour to submit herewith, for sanction of Government, an estimate, amounting to Rs. 2,600, for fixing cast iron pipe sluices along the Nerur channel, together with a re-sluicing statement.

This estimate has been prepared at the request of the Collector for utilizing the balance of Irrigation Cess Fund available for expenditure on this channel.

ENCLOSURE.

REPORT to accompany the estimate for fixing cast iron pipe sluices along the Nerur channel No. 46.

| | Rs. |
|---|---|
| Amount of estimate ... ... ... ... ... ... ... | 2,600 |

2. The estimate has been prepared with reference to the Superintending Engineer's letter No. 537 C.I., dated 23rd September 1896, on Collector's letter No. 3365-Rev., dated 10th September 1896.

3. The existing sluices in the channel are 116 in number and it is proposed to replace them with 7 existing masonry sluices, which are in good order and require little repairs, and with 41 new cast iron pipe sluices.

4. The proposed pipe sluices are simply to be laid in the ground with one foot puddle wall all round without any masonry at their heads.

5. The discharge provided is at the rate of 40 acres per cubic foot per second.

6. The size of the sluices has in every case been made larger than that arrived at theoretically to avoid all complaints and litigation and because the levels of the land to be irrigated often vary greatly.

16th April 1898.

(Signed) A. A. G. MALET,
Ex. Engineer, Coimbatore Divn.

No. 163 I.

*Note by the Chief Engineer for Irrigation.*

The Superintending Engineer, IV Circle, applies for sanction to the accompanying estimate, amounting to Rs. 2,600, for fixing cast iron pipe sluices along the Nerur channel, Coimbatore division.

2. The estimate may be sanctioned.

9th May 1898.

(Signed) W. HUGHES,
Chief Engineer for Irrigation.



ORDER—No. 433 I., dated 3rd June 1898.

The following estimate is sanctioned:—

Local Irrigation Cess Fund.
43. Minor Works and Navigation.
Minor Works for which neither Capital nor Revenue Accounts are kept.
Original Works.
Coimbatore Division.
Fixing cast iron pipe sluices along the Nerur Channel.

| | Rs. |
|---|---|
| Estimate ... ... ... ... ... ... ... ... ... | 2,600 |

2. This sanction is registered as No. 42 I. of 1898–99.

(True Extract.)

Under Secretary to Government,
~~Irrigation~~ Branch.

To the Chief Engineer for Irrigation.
" Superintending Engineer, IV Circle, with three enclosures.
" Examiner, Public Works Accounts.
" Revenue Department.

Ex1. C. M. Thumbusawmy.

*hen given for copying*
*Then copied*
*Then examined*
*Then signed*
} 189

e.

D AGAIN G.O., No. DATED
189 ,

EXEMT No.

NCLOSURES TO C. No.

| | | | | | | | | |
|---|---|---|---|---|---|---|---|---|
| ORDER OF GOVERNMENT .. .. .. | A | A | A | A | A | A | A | |
| LETTER OF GOVERNMENT. | | | | | | | | |
| STATEMENT WITH DITTO | | | | | | | | |
| PAPERS NOT FILED UP, BEING MEANT FOR DESPATCH IN ORIGINAL. | | | | | | | | |

*N.B.*—
A = Copy in full.
B = Not to be copied.
P = Copy abstract only.
Q = Copy heading only.