

Revenue (1899) Department.

MISCELLANEOUS SERIES.

G.O., No. 1580

DATED 27th April.

[Despatch Abstract.]

Coming: to the Bd. of Revs.,
Procs of the P.W.D., sanctioning with
remark revised estimate of Rs.
4130 for improving the Subjail at-
tached to the Sub-magistrate's Court
at Tiruvadi, Tanjavur Dt.

BACK PAPERS.

G.O.	No.	Department.	Date.	G.O.	No.	Department.	Date.

FURTHER PAPERS.

G.O.	No.	Department.	Date.	G.O.	No.	Department.	Date.

Revenue (1899) Dept.

BUILDINGS AND ROADS.
CIVIL WORKS.

Government {1899} of Madras.
PUBLIC WORKS.

Circuit No. 2640.



Recd. 19th April

1899.

Regd. 20th do.

Enclosures

Spare copies

G.O., No. 999 W., 8th April 1899.

APRIL. G.O. No. 1580 of 27th April 99
Communicated to the
Board of Revenue.

27th April 99

16 To the Board of Rev (Land Rev).
24-4-99

Sub-Jail attached to the Sub-Magistrate's Court at Tiruvadi
Revised estimate of Rs. 4,130 for improving the —, Tanjore district, sanctioned,
with remark.

24/4/99

GOVERNMENT OF MADRAS.

PUBLIC WORKS DEPARTMENT.

Buildings and Roads.
Civil Works.

READ—the following papers:—

From Colonel C. C. RAWSON, R.E., Superintending Engineer, V Circle, to the Chief Engineer, Public Works Department, dated Chepāk, 23rd February 1899, No. 131 W.

I have the honour to submit for sanction the enclosed plan and revised estimate, amounting to Rs. 4,130, with comparative statement for improving the sub-jail attached to the Sub-Magistrate's court at Tiruvādi in Tanjore division, showing an excess of Rs. 780 over the original estimate sanctioned in G.O., No. 2709 W., dated 29th September 1897, for Rs. 3,350.

The plan and revised estimate have been countersigned by the Collector of Tanjore.

The necessity for the revision of the estimate is explained in the remark column of the comparative statement and in the report attached to the estimate.

Note by the Chief Engineer, Public Works Department.

In G.O., No. 2709 W., dated 29th September 1897, an estimate, amounting to Rs. 3,350, for improving the sub-jail attached to the Sub-Magistrate's court at Tiruvādi, was sanctioned.

The Superintending Engineer, V Circle, with his letter quoted above, submits a revised estimate for Rs. 4,130, together with a comparative statement, showing an excess of Rs. 780, or 23.28 per cent. over the original estimate. The excess is due to the following causes:—

(a) Increase in quantity	...	...	...	...	...	...	Rs.
(b) Deviation in material	...	...	...	...	...	...	306
(c) Trifling excesses in various sub-heads	...	...	...	...	...	...	443
							92
						Total	841
						Deduct sum due to savings	61
						Net excess	780

The increase due to (a) is shown in the following table:—

Sub-heads.	Quantity in sanctioned estimate.	Quantity in revised estimate.	Remarks.
Concrete with brick jelly in mortar for foundations.	C. FT. 197	C. FT. 1,690	The dwarf walls, for which provision was made in the estimate for raising, were provided with no foundations. These have now been provided similar to the foundations provided for cross walls. 4" concrete is proposed to be laid under Cuddapah slabs for flooring. Hence increase. Extra quantity due to height of basement for dwarf walls.
Brick in chunam with platform moulded bricks.	4,373	5,226	

The officer, who originally prepared the estimate, was of opinion that the dwarf walls might be built on the floor without foundations. It was afterwards concluded that this should not be done; hence the excess in foundations.

Item (b).—The original estimate made no provision for flooring the wards, except a lump sum provision of Rs. 5. As the asphalt floor is damaged, it is now proposed to lay 2" Cuddapah slabs over a bed of 4" concrete pointed with asphalt.

Item (c).—Calls for no remark.

(Signed) A. W. SMART, Colonel, R.E.,
Ag. Chief Engineer.

17th March 1899.

ORDER—No. 999 W., dated 8th April 1899.

The revised estimate, amounting to Rs. 4,130, for improving the sub-jail attached to the Sub-Magistrate's court at Tiruvādi, Tanjore district, is sanctioned in supersession of the estimate of Rs. 3,350 sanctioned in G.O., No. 2709 W., dated 29th September 1897.

2. There is a provision of Rs. 2,500 for the work in the current year. The balance of the estimate will be allotted in the final issue of the Provincial Civil Works budget for 1899-1900.

3. This sanction has been registered as Provincial No. 3 W. of 1899-1900 and classified as Civil Buildings—Original Works.

(True Extract.)

A. W. Smart

Under Secretary to Government.

To the Superintending Engineer, V Circle,
with five enclosures.

" Examiner, Public Works Accounts.
" Revenue Department. ✓

W. S. Karim

Exd. Shaik Karim.

When given for copying _____
When copied _____
When examined _____
When signed _____

189 .

READ AGAIN G.O., No.
189

DATED

CURRENT No.

ENCLOSURES TO C. No.

ORDER OF GOVERNMENT

LETTER OF GOVERNMENT.

DOCUMENT WITH DITTO.

PAPERS NOT FILED UP, BEING MEANT FOR DESPATCH
IN ORIGINAL.

N.B.—

A = Copy in full.
B = Not to be copied.
P = Copy abstract only.
Q = Copy heading only