Revenue (1898) Department.

MISCELLANEOUS SERIES.

G.O., No. 4430

DATED 14th Nov. 98

[Despatch Abstract.]

Communicating to the Board of Revenue G.O. Public Works Dept. Sanctioning with remark, estimate of Rs 40. 650 for constructing a Taluk office at Tirutturaipundi in the Tanjore Dt.

BACK PAPERS.

G.O.	No.	Department.	Date.	G.O.	No.	Department.	Date.

FURTHER PAPERS.

G.O.	No.	Department.	Date.	G.O.	No.	Department.	Date.
enc	146/98			P	2714	Rev	24-7-98

Revenue Dept

BUILDINGS AND ROADS.
CIVIL WORKS.

Government {1898} of Madras.

PUBLIC WORKS.

Contract No. 7596

Recd. 5/11 } 1898. *Enclosures*

Regd. 7/11 *Spare copies*

G.O., No. 2692 W., 15th October 1898.

SECRETARIAT 15 NOV 98 REV. DEPT.

OCTOBER. ~~G.O. Endt~~ No. 4430 7/14 Nov 1898 Communicated to the Board of Revenue.

RS 11-11-98

W 14/11/98

17/o the Board of Rev (Land Rev).
GS 7-11-98 RS 16-11-98

Taluk Office at Tirutturaippundi

Estimate of Rs. 40,650 for constructing a — in the Tanjore district, sanctioned, with remark, for execution when funds are available.

GOVERNMENT OF MADRAS.

PUBLIC WORKS DEPARTMENT.

Buildings and Roads.
Civil Works.

Read—the following papers:—

Proceedings of the Board of Revenue (Land Revenue), Mis. No. 2176, dated 13th August 1898.

Read—endorsement of the Acting Collector of Tanjore, dated 1st August 1898, Dis. No. 3389-Rev., on letter from the Superintending Engineer, V Circle, dated 4th July 1898, No. 233 M.

Resolution—Mis. No. 2176, dated 13th August 1898.

The plan and estimates forwarded by the Collector of Tanjore for the construction of a new taluk cutcherry at Tirutturaippúndi are submitted to Government in the Public Works Department with reference to its order, No. 2375 W., dated 17th August 1896.

2. The Collector's attention is drawn to paragraph 4 (*f*) of Board's Proceedings, No. 232, dated 26th June 1896, under which the plan and estimates should have been submitted to Government direct.

(True Extract.)

(Signed) LIONEL DAVIDSON,
Acting Secretary.

Note by the Chief Engineer, Public Works Department.

For ceiling planks under Mangalore tiles, flat tiles over reepers 2″ × ½″ should be substituted, the Mangalore tiles being imbedded in mortar laid over the flat tiles of sufficient thickness to secure them in position.

2. Steel girders should be substituted for the four wooden beams in the three wards and the Police guard-room.

3. The data submitted with the estimate show Rs. 40 as the rate per square of flooring with Cuddapah slabs on 4″ concrete, but in the estimate Rs. 45 have been allowed. The necessary correction has been made in the estimate.

4. An error of Rs. 374 in addition occurs in page 7 of the abstract estimate. This has been rectified. The Superintending Engineer's particular attention is called to this, as it is not the duty of this office to check the arithmetical accuracy of estimates.

5. The estimate has been reduced from Rs. 42,400 to Rs. 40,650 by the above alterations and corrections, and is recommended for sanction.

16th September 1898.

(Signed) W. B. DEWINTON,
Chief Engineer.

Order—No. 2692 W., dated 15th October 1898.

The estimate amounting to Rs. 40,650, as altered by the Chief Engineer, for constructing a taluk office at Tirutturaippúndi in the Tanjore district, is sanctioned for execution when funds are available.

2. Attention is drawn to the Chief Engineer's note read above.

3. This sanction has been registered as Provincial No. 73 W. of 1898–99, and classified as Civil Buildings—Original Works.

(True Extract.)

Under Secretary to Government.

To the Superintending Engineer, V Circle,
with seven enclosures.
„ Examiner, Public Works Accounts.
„ Revenue Department.

Exd. T. K. Narayana Aiyangar.

When given for copying ____
When copied ____
When examined ____
When signed ____ } 189 .

READ AGAIN G.O., No. , DATED
189

CURRENT No.

ENCLOSURES TO C. No.

ORDER OF GOVERNMENT	A	A	A	A	A	A	A
LETTER OF GOVERNMENT.							
STATE[illegible] WITH DITTO.							
PAPERS NOT FILED UP, BEING MEANT FOR DESPATCH IN ORIGINAL.							

N.B.—
A = Copy in full.
B = Not to be copied.
P = Copy abstract only.
Q = Copy heading only.